

Analisa penyebab kecelakaan kerja pada saat handling dan rigging pipa baja

Bawono, Tejo

Deskripsi Lengkap: <https://lib.fkm.ui.ac.id/detail.jsp?id=44730&lokasi=lokal>

Abstrak

Kecelakaan adalah kejadian yang tidak diinginkan atau serangkaian kejadian (atau adanya potensi penyebab) cedera, sakit dan kerusakan. Penanganan (handling) dan pemunggahan (rigging) pipa baja, material dan peralatan merupakan pekerjaan yang berbahaya. Setiap pekerjaan tersebut menghadirkan masalah tersendiri, dengan pertimbangan yang matang dan praktek pemunggahan yang benar, setiap pekerjaan dapat dihindari resiko kecelakaan pada manusia atau kerusakan pada peralatan. Biaya yang timbul akibat kecelakaan mencapai lebih dari 500 juta rupiah. Terdapat 5 (lima) kecelakaan major yang terkait dengan kejadian selama penanganan dan pengiriman pipa baja. Hal ini terjadi pada awal pengiriman terjadi beberapa kecelakaan oleh kontraktor dengan lokasi kejadian yang berbeda. Dan hasil penyelidikan, diketahui penyebab kecelakaan pada crane 80 ton di Bintan secara teknis disebabkan crane tidak mampu menahan pembebanan berlebih (overload) secara terus menerus sehingga crane mengalami fatigue (kelelahan) akibat beban dinamik yang terjadi secara siklus. Pada crane yang menggunakan tipe teleskopik, sangat berisiko terjadi patah pada bagian (section) ruas boom crane, yang apabila jika pembebanan melewati SWL (safe working load) akan menyebabkan bagian boom crane tersebut fracture. Penyebab lainnya (contributing causes) adalah penggunaan peralatan yang rusak dan tidak layak pakai, hilangnya pelindung keselamatan, peralatan keselamatan yang kurang memadai dan kesalahan dalam pemuatan. Audit kinerja keselamatan kerja dari masing-masing subkontraktor memperlihatkan tingkat kinerja keselamatan yang rendah seperti lemahnya prosedur kerja aman, keterlibatan manajemen, perawatan peralatan dan pemeriksaan internal.

An accident is an undesired event or sequence of events (or with the potential to cause) injury, ill-health or damage. The handling and rigging of steel pipes, material and equipment is a hazardous occupation. Each operation presents its own peculiar problems and no two jobs are alike. With proper consideration and good handling practices taken, each job can be performed free of body harm and without damage to the equipment: There were 5 (five) work accident related with handling and delivery of steel pipes (32" OD) in December 2005 up to May 2006. It was found mostly on early delivery during pipe handling was carried out by each subcontractor at various location. The cost impact after accident more than 500 billion rupiah and one rigger injured. By accident investigations were performed technically the crane could not withstand the continuously overload and occur fatigue due to dynamic load cyclically. The telescopic crane had high risk during loading over safe working load (SFL) which cause boom crane will be fractured. The contributing causes of this event are using defective equipment, removing safety devices or inadequate / improper protective equipment, and improper loading. As indicated before, the audit safety performance has been carried refer to Roman Diekemper and Donald Spartz. Mostly subcontractor shows that bad safety performance includes safe working procedures, direct management involvement, maintenance of equipment guards and internal self-inspection.