

Manajemen Risiko Keselamatan Kerja pada Proses Kegiatan Perancah di Senayan Square Hotel Complex PT X Tahun 2012

Fitriani, Hasnah

Deskripsi Lengkap: <https://lib.fkm.ui.ac.id/detail.jsp?id=90201&lokasi=lokal>

Abstrak

Perancah merupakan komponen sementara dalam pengerjaan struktur di sektor konstruksi. Pekerja harus memanjat dan beradadiketinggian ketika bekerja pada perancah. Proyek Senayan Square meskipun belum terjadi Kecelakaan kerja pada perancah namun memiliki potensi risiko yang cukup tinggi dari risiko terjatuh, tergelincir, tertimpa frame tangan terjepit dan perancah ambruk . Penelitian ini adalah penelitian semi kuantitatif menggunakan metode pendekatan Risk Management AS/NZS 4360: 2004 dalam penilaian Risiko. Metode yang digunakan adalah untuk menentukan tingkat risiko Keselamatan dan Kesehatan kerja dalam tahapan pekerjaan perancah di senayan square hotel complex khususnya pada proses pemasangan dan pembongkaran Perancah. Pengumpulan data dilakukan dengan observasi, wawancara dan telaah dokumen pada unit PT.X.. Hasil penelitian menunjukkan bahwa implementasi pada proses perancah sudah memiliki sistem Manajemen Risiko yang baik, namun risiko terjatuh memiliki potensi risiko 40 % dan tergelincir dan perancah ambruk memiliki potensi risiko 40 %. yang perlu pengawasan lebih lanjut. Kata kunci : Manajemen, Risiko, Perancah

Scaffolding is temporary component in construction. Workers have to climb and stand on above scaffolding. Safety aspects of the activities scaffold must be considered both at the stage of setting up and dismantling. The process of scaffolding activities have potential hazards such as falls, pinched, slip, and hit the main frame. his research is a semi-quantitative approach using Risk Management AS / NZS 4360: 2004 Risk assessment. The method used is to determine the level of risk in the workplace Health and Safety in Senayan stage scaffolding work square hotel complex especially proses scaffold erection and dismantling. Data was collected through observation, interviews and document review at unit PT. X. The results showed that the implementation on the scaffold already have a good risk management system, but the risk has fallen 40% and the potential risk of slipping and collapsing scaffolds have the potential risk of 40%. that need further security. Key word: Management, Risk, Scaffolding